FENETEX
RETRACTABLE SCREENS

Quote Date 06-08-2022 09:18 AM
Quote Id 30043-FCMH-DIYT
Sidemark DIYTonyGieselConstruction
Tracking#

FENETEX
, 259 Ellis Road S Jacksonville, FL, 32254, US
+1 561 324 8840, anzulis@fenetex.com

Sold To: Fenetex Contractor (MH)
Residential
259 Ellis Road South
JACKSONVILLE, FL, 32254, United States
+1 904 684 7361
ContractorMollee@fenetex.com

Ship To: Fenetex Contractor (MH)
259 Ellis Road South
JACKSONVILLE, FL, 32254, United States
+1 904 684 7361
ContractorMollee@fenetex.com

Order Details

#	Qty	Name of Product	Price
1	1	**Retractable Screen Systems**, **Shade Screen** Nano95 BLACK W : 61 3/8 INCHES H : 97 5/16 INCHES Angled Bottom : No Track Type : One-Track Track Color : Bronze (MB) Operator : FENETEX SMART MOTOR (25Nm) Operator Location : Left Housing Styles : Hoods 5.5 in Hood w/4 in reel : , Bronze (MB) Weight Bar : Weight Bar Standard Weight Bar Color : Bronze (MB)	$1,359.08

Special Instruction: Deduction of 3/8" taken per CL.

2	1	**Retractable Screen Systems**, **Shade Screen** Nano95 BLACK W : 61 9/16 INCHES H : 97 9/16 INCHES Angled Bottom : No Track Type : One-Track Track Color : Bronze (MB) Operator : FENETEX SMART MOTOR (25Nm) Operator Location : Left Housing Styles : Hoods 5.5 in Hood w/4 in reel : , Bronze (MB) Weight Bar : Weight Bar Standard Weight Bar Color : Bronze (MB) **Special Instruction:**Deduction of 3/8" taken per CL.	$1,361.92
3	1	**Retractable Screen Systems**, **Shade Screen** Nano95 BLACK W : 299 5/8 INCHES H : 97 5/16 INCHES Angled Bottom : No Track Type : One-Track Track Color : Bronze (MB) Operator : FENETEX SMART MOTOR (50Nm) Operator Location : Left Housing Styles : Hoods 7 in Hood w/5.5 in reel : , Bronze (MB) Weight Bar : Weight Bar Heavy Weight Bar Color : Bronze (MB) **Special Instruction:**Deduction of 3/8" taken per CL.	$4,009.91
		CONTROLLERS	
1	2	Fenetex 15 Ch Remote	$76.14
		COMPONENT	
		2 x 2 x 1/8 x 20' 6063 Angle BRONZE (11-MB-376)	
1	3	**Note:** CL confirming qty and cut lengths	$278.88

TOTAL	QTY	WIDTH	HEIGHT	SQFT	PRICE
	8	422.5625 inches	292.1875 inches	285.67	$ 7,085.93

SALES TAX (0%)	:	$0.00
SUB-TOTAL	:	$7,085.93
GRAND TOTAL	:	$7,085.93
AMOUNT RECEIVED	:	$0.00
DUE	:	$7,085.93

Prices are good for 30 days from the date of quote.

Hurricane screens are manufactured per Florida Product Approval #FL 8637. FL8637 is only valid when products are ordered and/or installed according to the Product Approval. Products ordered and/or installed outside the scope of the Approval require site specific engineering (SSE) for use as a hurricane protective system. Design professionals may use the Approval noted herein as a basis for SSE. Determination of use is the sole responsibility of purchaser.

Warranty is void for any service or functionality related issues or damage that may arise from non-standard screens. Non-standard screens include, but are not limited to:
•Hurricane Screens outside the Florida Product Approval;
•Any screen ordered outside the recommendations in the Fenetex Design Guide (examples include: very wide screens may have excessive deflection in the reel tube causing wrinkles in the screen, very tall screens may not roll up evenly, very narrow screens may not have enough weight to operate smoothly, very large screens may not withstand as much wind load and may be more prone to damage as a result);
•Any screen using a manual gear (may back roll on reel and damage screen);
•Any clear screen made outside Fenetex's recommended layout (screen may stick to itself when rolled up).
Other warranty items for materials and workmanship remain in effect except where excluded herein.

Your signature on this document is your acceptance of these terms herein. Customer is solely responsible for any loss or damage. If Dealer is a corporation, LLC, partnership, or other artificial entity, the undersigned person hereby personally and unconditionally guarantees punctual payment by Dealer as required by this Agreement.

NO EMPLOYEE, DISTRIBUTOR, OR REPRESENTATIVE IS AUTHORIZED TO CHANGE THE FOREGOING WARRANTIES IN ANY WAY OR GRANT ANY OTHER WARRANTY ON BEHALF OF THE COMPANY.